F.D. Road Dist. No.	State	County	S.C. Docket No.	Route No.	Sheet No.	Total Sheets
14	S.C.	ABBEVILLE	7220	184	2	9

THE ROAD CONTRACTOR WILL CLEAR AND GRUB THE RIGHT-OF-WAY ADJACENT TO THE BRIDGE AS SHOWN BY CROSS HATCHED LINES. THE BRIDGE CONTRACTOR WILL CLEAR AND GRUB AREA AS SHOWN BY BROKEN LINES.

ESTATE OF MRS LEON L. RICE

CITY OF ABBEVILLE

BEN C. THORNTON

SURVEY STA 127+20.58 END OF S.C. DOCKET 1.220 AND BEGINNING OF F. A. S. PROJ. NO. 63-A(1) PT. 2

STA. 122+00 END F.A.S. PROJ. 63-A(1) PART 1.
BEGIN S.C. DOCKET 1.220

ESTATE OF MRS. LEON L. RICE

Place 160 lin. ft. of 24" pipe on 30° skew. Butted at Headwalls as shown on Sheet No. 8. Use extra strength Pipe. See Special Provisions.

Place 60 lin. ft. of 18" pipe Culvert on 30° skew. Butted at Headwalls as shown on Sheet No. 8.

RIVER

ABBEVILLE ANDERSON

S.C. DOCKET 1.220
320.58 FT. BRIDGE TO BE CONSTRUCTED FROM STA. 122+00 TO STA. 127+20.58

P.I. = 124+89.5 (No Ref.)
Δ = 4°-48'-ET
D = 0°-30'
T = 480.2
L = 960.0
E = 10.08

P.C. = 120+08.8
P.T. = 129+68.3

PLATE I-PLAN-PROFILE

EUGENE DIETZGEN CO. CHGO. N. Y.